

2021 STREET CONSTRUCTION

Bulletin No. 3

July 2, 2021



Phase 2 of the 2021 Street Improvement Program is anticipated to begin on July 6th by the Village's contractor Schroeder Asphalt Services, Inc. See attached Location Map of streets included in Phase 2 of this year's program.

This project consists of the grinding and resurfacing of the deteriorated roadway segments and concrete removal and replacement when warranted. Specifically, the construction sequence will be as follows:

1. Intermittent Sidewalk, Curb & Gutter, and driveway removal and replacement.
2. Underground utilities work. (Utility Frame Adjustment, Structure Reconstruction)
3. Asphalt surface removal. (Grinding)
4. Asphalt patching of failed base course.
5. First layer paving with Hot-Mix Asphalt Leveling Binder.
6. Final layer paving with Hot-Mix Asphalt Surface Course.

During construction, roads will remain open and driveway access will be maintained. The Village will work closely with the contractor to minimize the inconvenience to you during the project. Phase 2 construction is scheduled to begin on July 6th and anticipated completion date is August 20th. Resident can expect varying level of construction activity during that timeframe.

Any property within the right-of-way such as irrigation systems, sprinklers and decorative landscaping that is damaged during construction is the responsible of the homeowner. It is the homeowners' responsibility to mark or flag any irrigation systems within the right-of-way prior to the start of construction. Please call or email the contact listed below prior to construction if you have any concerns.

Weather permitting; our street contractor will begin the intermittent sidewalk, curb & gutter, and driveway removal and replacement work on or after July 6th. Prior to concrete removals that will affect driveway access, our contractor will be notifying the affected residents to remove all vehicles from their garage and park them on the street. Driveway access will be restricted for approximately one week while the concrete is removed, poured, and allowed to cure. The police will be notified and parking on the street or an adjacent street will be allowed in those cases.

Keeping residents informed about the progress of the Village's Street Improvement program is very important to us. In addition to this bulletin, we are posting regular construction updates on the Village's website at www.roselle.il.us/construction. Updates can also be found in the Village's weekly E-News digital newsletter (subscribe at www.roselle.il.us/enews) and on the Village' official Facebook page.

We apologize for the inconvenience created during construction and thank you for your patience and cooperation. For questions or concerns about the construction, please do not hesitate to contact Matthew Rasmussen at 630-671-2366 or e-mail at mrmussen@roselle.il.us.

Karen Young, Director of Public Works
Kristin Mehl, Assistant Director of Public Works/Village Engineer

474 Congress Circle North • Roselle, Illinois 60172-3904
Telephone: (630) 671-2360 • Fax: (630) 582-6035 • www.roselle.il.us